



Sound pressure level at the workplace no load  $L_{pA}$ : 92,8 dB(A)  
 Sound pressure level at the workplace load  $L_{pA}$ : 98,5 dB(A)  
 Measured sound power level  $L_{WA}$ : 109,6 dB(A)  
 Guaranteed sound power level  $L_{WA}$ : 114 dB(A)  
 Measurement uncertainty K: 4 dB(A)

## Construction circular saw BTK 400



230 V ~ 50 Hz  
400 V ~ 50 Hz



Ø 400 x 2,8/3,8 x  
Ø 30 mm - 28 teeth



$P_1$  3000 W (S6-40%)  
 $P_2$  2200 W (S6-40%)  
 $P_1$  4400 W (S6-40%)  
 $P_2$  3500 W (S6-40%)



N.W. 108,0 kg G.W. 108,0 kg  
1050 x 750 x 1130 mm

- hinged rip fence
- cross- and calibrated mitre fence, as well as aluminium stop bar
- cutting height approx. 126 mm
- dust suction outlet
- hinged table extension approx. 720 mm
- fully galvanised & lifting hooks
- CEE-plug with phase-shifting for 3-phase operation

AC brake motor  $P_1$  3000 W, assembled  
Order No. 303150



3-phase brake motor  $P_1$  4400 W, assembled  
Order No. 303160

